

Work Order Bid (Amended Training House) (ID) 561 Bonita

WORK ORDER INFORMATION

Work Order Name: WO/26026MH10085/1

Work Order Type: Weatherization

Audit Name: 26026MH10085 Part 1 Pre Audit

CLIENT INFORMATION

Client ID: 26026MH10085

AGENCY INFORMATION

Agency: Memphis Housing & Community Development

Address: 170 North Main St.
Memphis, TN 38103

Agency Contact: CHP, Thom P

Agency Phone: (901) 636-7300

Fax: (901) 636-7318 xor 7434

Email Address:

Work Phone:

Cell Phone:

Email Address:

Company Name && License

Contractor's Signature:

COMMENT

DUE TO SEPARATE DUCT SYSTEMS, THIS HOUSE HAS BEEN MODELED IN TWO PARTS. THE BLOWER DOOR NUMBER IN THE MODEL IS PROPORTIONAL TO THE SF, BUT THE NUMBER BELOW IS FOR THE WHOLE HOUSE. CONTRACTORS MUST SPECIFICATIONS INDICATED IN LINKS PROVIDED.

Blower Door: 5347 CFM
Target 3354 CFM

Measures

Measure 1 Floor Ins. R-19

Components F1

Inspected

Comment INSTALL FACED INSULATION WITH FACED SIDE IN CONTINUOUS CONTACT WITH THE FLOOR.
<https://sws.nrel.gov/spec/413011>

#	Material / Labor	Description /	Units	Qty	Estimated		Actual	
					Unit Cost	Total	Qty	Unit Cost
1	Insulation	Floor Insulation - Fiberglass Batts - R-19	Sq Ft	975				
2	Labor	Floor Insulation - Fiberglass Batts - R-19	Sq Ft	975				

Other Detail

Measure Sub Total:

Sub Total:

Field Notes:

Measure 2 Low-E Windows

Components N1, N2

Inspected

Comment INSTALL REPLACEMENT WINDOWS AND AIRSEAL PERIMETER AS PER MANUFACTURER'S SPECIFICATIONS.

#	Material / Labor	Description /	Units	Qty	Estimated		Actual	
					Unit Cost	Total	Qty	Unit Cost
1	Windows	Low E Window	Sq. Ft	26.444				
2	Labor	Low E Window	Sq. Ft	26.444				
3	Other	Low E Window	Each Window	2				

Other Detail

Measure Sub Total:

Sub Total:

Field Notes:

Measure 3 Attic Ins. R-19

Components A2

Inspected

Comment CURRENTLY THE WHOLE ATTIC IS FLOORED, BUT UNUSED. LEAVE 8' X 16" SECTION FLOORED FOR ACCESS TO DHW AND FURNACE, AND REMOVE REMAINDER OF FLOORING FOR ADDING INSULATION. DO NOT SIMPLY ADD INSULATION ONTOP OF FLOOR, AS THIS WILL RENDER IT INEFFECTIVE.
<https://sws.nrel.gov/spec/4>

#	Material / Labor	Description /	Units	Qty	Estimated		Actual	
					Unit Cost	Total	Qty	Unit Cost
1	Insulation	Attic Insulation - Blown Fiberglass - R-19	Sq. Ft	847				
2	Labor	Attic Insulation - Blown Fiberglass - R-19	Sq. Ft	847				
3	Miscellaneous	Attic Insulation - Blown Fiberglass - R-19	Each	1				
4	Miscellaneous	Added Misc. Cost	Each	1				

Other Detail

Measure Sub Total:

Sub Total:

Field Notes:

Measure 4 INSTALL 30 KBTU ENERGY STAR GAS PACKAGE UNIT

Components

Inspected

Comment CURRENT UNIT IS OVERSIZED. SPACE REQUIRES SMALLEST PACKAGE UNIT AVAILABLE.

#	Material / Labor	Description	Units	Qty	Estimated		Actual	
					Unit Cost	Total	Qty	Unit Cost
10	Unspecified	30 KBTU ENERGY STAR GAS PACKAGE UNIT	Each	1		\$		

Other Detail

Measure Sub Total:

Sub Total:

Field Notes:

Measure 5 Floor Ins. R-19

Components F1

Inspected

Comment INSTALL FACED INSULATION WITH FACING IN CONTINUOUS CONTACT WITH FLOOR.
<https://sws.nrel.gov/spec/413011>

#	Material / Labor	Description /	Units	Qty	Estimated		Actual	
					Unit Cost	Total	Qty	Unit Cost
1	Insulation	Floor Insulation- Fiberglass Batts - R-19	Sq Ft	702				
2	Labor	Floor Insulation- Fiberglass Batts - R-19	Sq Ft	702				

Other Detail

Measure Sub Total:

Sub Total:

Field Notes:

Measure 6 INSTALL ASHRAE FAN IN BATHROOM

Components

Inspected

Comment <https://sws.nrel.gov/spec/660031>
VENT THROUGH ROOF. HAVE PROFESSIONAL ROOFER INSTALL ROOF LOUVER AS PER MANUFACTURER'S SPECS. NO FASTENERS SHALL BE VISIBLE EVEN IF COVERED WITH CAULK. REQUIRED CONTINUOUS VENTILATION 20 CFM. FAN SHALL HAVE UNSWITCHED CONTINUOUS POWER AND CIRCUIT BREAKER SHALL BE LABELED. WALL SWITCH OR MOTION SENSOR MAY BE USED FOR BOOST.

#	Material / Labor	Description /	Units	Qty	Estimated		Actual	
					Unit Cost	Total	Qty	Unit Cost
10	Unspecified	ASHRAE FAN, VENTING, ROOF LOUVER	Each	1				

Other Detail

Measure Sub Total:

Sub Total:

Field Notes:

Measure 7 VAPOR BARRIER

Components

Inspected

Comment <https://sws.nrel.gov/spec/204032>

#	Material / Labor	Description /	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
10	Unspecified	1 ROLL OF 6 MIL BLACK PLASTIC, ADHESIVE/SEALANT	Each	1					

Other Detail

Measure Sub Total:

Sub Total:

Field Notes:

Work Order Grand

Grand Total: