

**CITY OF MEMPHIS – STANDARD CONSTRUCTION SPECIFICATIONS
SECTION 01550 – VEHICULAR ACCESS AND PARKING**

PART 1 – STREET NAME MARKERS AND TRAFFIC CONTROL SIGNS

1.01 Street name markers are to be maintained by the Contractor during the construction period. If construction requires removal of any street name markers, the Contractor shall temporarily reinstall the markers as near the intersections as possible. When construction is completed, the Contractor shall reinstall any markers removed at a location designated by the Owner, except that if the marker is a concrete post it shall be removed and disposed of by the Contractor.

1.02 All regulatory signs shall remain in service unless otherwise approved by the Owner. Existing STOP, YIELD, ONE WAY, DO NOT ENTER, TURNING PROHIBITION, and other regulatory signs are to be maintained by the Contractor during the construction period. All regulatory signs shall remain in service unless approved by the Owner. If any such signs must be removed or temporarily relocated during any phase of the construction, the Contractor shall notify the Owner and receive his approval before removing or relocating signs. The Contractor shall provide temporary signing to replace those removed or replaced as directed by the Owner. The contractor shall notify the Owner when construction has progressed to the point where any such signs removed or relocated can be returned to their proper locations.

1.03 The Contractor shall furnish, install, and remove any temporary parking restriction signs required for construction.

PART 2 – CONSTRUCTION TRAFFIC CONTROL DEVICES

2.01 Where any land or section of road, street, or highway is closed for construction operations of any type, or when traffic is to be maintained along a road, street, or highway under construction or affected by construction activities, or when any section thereof is opened to traffic prior to completion of all Work on the section, the Contractor shall protect the workers and provide for safe and convenient public travel by providing, erecting, and maintaining to the satisfaction of the Owner and in accordance with the Traffic Control Plan all signs, signals, markings, barricades, warning lights, flaggers, and other traffic control devices required for the type of operation being performed. Construction traffic control devices shall be provided by the Contractor according to the requirements of the Plans and Sections 02890 and 02891 of these Standard Construction Specifications.

2.02 Where detours are used, detour signing meeting the requirements of MUTCD shall be placed along the approaches and complete route of the detour and maintained for the course of the Work. Detour signing shall be included in and installed and maintained according to the Traffic Control Plan.

2.03 Closure of a road, street, or highway to all but local traffic will not relieve the Contractor of the responsibility to provide for safe and convenient public travel. The Contractor shall provide, erect, and maintain according to the Traffic Control Plan and to the satisfaction of the Owner, all traffic control devices necessary to protect the Work and to safeguard local traffic.

PART 3 - COMPENSATION

3.01 The expense to the Contractor in fulfilling the obligations of this Specification are considered as incidental to the Work of the Contract and no direct compensation will be allowed except that payment to the Contractor for traffic control devices used will be made by the Owner according to Sections 02890 and 02891 of these Standard Construction Specifications.

END OF SECTION 01550